

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Missaukee</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>5W</u>	<u>MC-47</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 9, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9									●				
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

MC-47 – **1852** – GLO – A. Curtis – N0°53'W Corr. between Sec. 26 & 27.
 77.91 Intersect Muskegon River and set post.
 W. Ash 12 S82°E 18 lks.
 Lynn 12 S38°E 34 lks.
 79.68 over trigonometrically and set post corner Sects. 22, 23, 26 & 27

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

MC-47 – Per GLO plat the meander corner on the left bank of Muskegon River being 1.77 chains South of section corner common to Sections 22, 23, 26 & 27. No conclusive evidence of GLO BT's or post. Set 2" Aluminum cap on 5/8" x 34" rebar by single proportion to GLO between 'I-9' and 'I-10'. S0°01'32"W 116.71' (116.82' – GLO) from 'I-9' to 'MC-47' and S0°01'32"W 2510.21 (2512.62' – GLO) to 'I-10', which is a calculated corner in river per K. J. Ostling 1967 DNR survey. North 17' to top of bank of river. 2" Aluminum Cap accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

MC-47 – Stamped 2" Aluminum Cap on 5/8" x 34" rebar
 N02°52'W 12.26' to fd. 4" concrete monument
 N82°E 15.65' to set nail and tag in North side 12" Oak
 S21°E 71.88' to set nail and tag in East side 19" Red Maple
 S57°W 37.98' to set nail and tag in Northwest 22" Red Maple
 Set Blue Carsonite Post with location tag 1' East
 North 17' to top of bank of river



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/18/2007