

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Missaukee Located In _____ Corner Code # _____
(County)

- | | | | | | | | | |
|--------------------------------------|---|---|------------|--|---|-----------|--|--------------|
| 1. Public Land Survey | | T | <u>22N</u> | | R | <u>5W</u> | | <u>MC-51</u> |
| | | T | _____ | | R | _____ | | _____ |
| 2. Property Controlling in Section | S | T | _____ | | R | _____ | | _____ |
| | S | T | _____ | | R | _____ | | _____ |
| 3. Miscellaneous Property in Section | S | T | _____ | | R | _____ | | _____ |
| | S | T | _____ | | R | _____ | | _____ |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 9, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9									●				
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

MC-51 – **1852** – GLO – A. Curtis – N0°53'W Corr. between Sect. 22 & 23.
4.34 over river trigonometrically and set post
Maple 18" N65°E 35 lks.
Do 8" N33°W 33 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

MC-51 – Per GLO plat the meander corner on the left bank of Muskegon River 4.34 chains north of Section Corner common to Sections 22, 23, 26 & 27 - No conclusive evidence of GLO BT's or post. Set 2" Aluminum cap on 5/8" x 34" rebar by single proportion to GLO between 'I-8' and 'I-9'. From 'I-9' N01°15'14"W 284.95' (286.44' – GLO) to 'MC-51' and N01°15'14"W 2330.76' (2343' – GLO) to 'I-8'. South 55'± to top of bank of river. 2" Aluminum Cap accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

MC-51 – Stamped 2" Aluminum Cap on 5/8" x 34" rebar
N48°E 9.38' to set nail and tag in Northwest side 22" Red Maple
S61°E 50.94' to set nail and tag in Southwest side 12" Red Maple in clump of 5
S47°W 27.66' to set nail and tag in Northwest side 11" Red Maple
N66°W 38.56' to set nail and tag in Northeast side 20" Oak
Set Blue Carsonite Post with location tag 1' East



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 12/18/2007