

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Missaukee (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>26</u> T <u>22N</u> R <u>5W</u>	<u>13</u>
	S <u>26</u> T <u>22N</u> R <u>5W</u>	<u>14</u>
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Feb. 28, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

13 - None 14 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

13 - SE 1/16 Cor. Sec. 26 - Set 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure.
A 1/2" rebar was found S86°16'E 9.00' of Set 2" Alum. Cap.

14 - S 1/16 Cor. common to Sec. 25 & 26 - Fd. Unreadable Cap on loose 1/2" x 4' long rebar w/ 1/2" x 18" rebar alongside in leather leaf marsh. Fits calculated position. Line of steel pipe W & N from corner. 1/2" x 4' long CIR accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

13 - Stamped 2" Alum. Cap on 5/8" x 34" rebar.
Set Blue Carsonite Post w/ loc. tag 1' SW
S86°16'E 9.00' to Fd. 1/2" rebar
West 3.43 to set N & T in N. side 5" R. Pine
N24°W 23.58' to set N & T in W. side 13" R. Pine
N71°E 15.50' to set N & T in S. side 13" R. Pine
South 21.77 to set N & T in W. side R. Pine

14 - Replaced 1/2" CIR and 1/2" rebar w/ stamped 2" Alum. Cap on 5/8" x 5' long iron rebar
East 0.25' to face steel fence post
N6°W 65.67' to set N & T in E. side 8" J. Pine
N40°W 46.68' to set N & T in NE side 4" J. Pine
S81°W 68.36' to set N & T in N. side 8" J. Pine
S24°W 66.63' to set N & T in E. side 4" J. Pine
Set Blue Carsonite Post w/ loc. tag 1' SE

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 12/18/2007