

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Missaukee Located In _____ Corner Code # _____
(County)

- | | | | | |
|--------------------------------------|-------------|--------------|-------------|-----------|
| 1. Public Land Survey | T _____ | R _____ | | |
| | T _____ | R _____ | | |
| 2. Property Controlling in Section | S <u>26</u> | T <u>22N</u> | R <u>5W</u> | <u>9</u> |
| | S <u>26</u> | T <u>22N</u> | R <u>5W</u> | <u>12</u> |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ | |
| | S _____ | T _____ | R _____ | |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Feb. 12, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

9 - None

12 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

9 - CE 1/16 Corner Sec. 26 - Set 2" Alum. Cap per Standard BLM procedure. Centerline of a 2-track is 39' North. A found eligible 1/2" CIR is N85°34'E 5.19' from 2" Alum. Cap that was rejected.

12 - CS 1/16 Cor.; Section 26 - Set 2" Alum. Cap per Standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

9 - Stamped 2" Alum. Cap on 5/8" x 3/4" rebar
Set Blue Carsonite Post w/ loc. tag 1' NW
S52°W 45.25' to set Nail & Tag (N & T) in SE side 15" R. Pine
South 34.40' to set N & T in W. side 6" Oak
N75°E 65.84' to set N & T in N. side 5" W. Pine
N20°W 50.73' to set N & T in W. side 7" W. Pine
N85°34'E 5.11' to Fd. 1/2" CIR - eligible

12 - Stamped 2" Alum. Cap on 5/8" x 3/4" rebar
S58°W 9.95' to set N & T in SE side 8" W. Pine
S11°E 7.59' to set N & T in E. side 14" J. Pine
N83°E 54.13' to set N & T in N. side 9" R. Maple
N1°E 67.63' to set N & T in W. side 12" W. Pine
SE 1' to set Blue Carsonite Post w/ loc. tag

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 12/18/2007