

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 22 N. R. 6 W.	H-7; I-7; K-9
2. PROPERTY CONTROLLING IN SECTION	T. 22 N. R. 6 W.	2
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 18, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- H-7 Set corner record meas. from what we take for 1911 NBT of record, which falls nearly in line with fence north.
  - I-7 Found corner as previously restored in 1911 survey of record. Two pine stump NBT's still in place.
  - K-9 Found previously established corner in road. Witnessed for the record.

2 Set corner by standard survey procedure for the subdivision of sections.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7	I-7	K-9
Set DNR Monument	Fd. well pt. set DNR Mon.	Fd. 1/2" bar in conc. raised
6" W. Pine S67°W 45.4	8" Maple in clump	w/5/8" bar & RLS Cap
8" Maple S22°E 40.55	5" Maple N14°E 47.7	(X) in 3'x3' rock
	S47°E 35.5	S34°W 42.8
		Nail in fence corner
		S39°E 49.6
2		
Set 5/8" Rod w/RLS Cap		
10" Maple S88°E 25.35		
18" Oak S22°E 55.0		

SIGNED BY Kenneth Ostling

DATE 9/4/80

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

MISSAUKEE COUNTY