

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY-----	T. 22 N. R. 6 W. ●	K-5; K-6; L-7
2. PROPERTY CONTROLLING IN SECTION 13	T. 22 N. R. 6 W. ●	10
3. MISCELLANEOUS PROPERTY IN SECTION-----	T.----- S. R.----- E. W.-----	
4. LOT NO.-----, RECORDED PLAT-----		
5. PRIVATE CLAIMS-----		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 27, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- K-5 Found 1" pipe at corner as established in previous local surveys.
- K-6 Set corner by proportionate measurement between section corners. Unable to fit NBT's of record anywhere in this area & must be error in the 1911 record.
- L-7 Restored corner M.P.O.L. between section corners. No evidence of previous corner.
- 10 Set by standard survey procedure for the subdivision of sections. Unable to fit NBT's of record in 1911 survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5	K-6	L-7
Left 1" pipe in place	Set DNR Monument	Set DNR Monument
Nail & tag 18" Maple N72°W 30.25	7" Oak S76°W 26.7	10" Oak N72°W 10.9
Nail & tag 18" Maple S21°E 43.78	4" Twin Oak S51°E 13.4	3" Maple S40°W 12.7
	Fence corner E 20'	
		10 Set 5/8" rod w/RLS Cap
		5" Twin Oak S88°W 21.7
		4" Oak N10°W 40.7

SIGNED BY Kenneth Ostling
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

DATE 9/4/80



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE _____
 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ MISSAUKEE COUNTY