

SURVEY & REMONUMENTATION

JAN 27 1999

LIBER 323 PAGE 1232

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#1283

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>06W</u>	<u>C-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN
RECORDED NOV 13 1998 9:50 AM
Paulyn Klare
REGISTER
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, J. Dean Geers, P.S., in a field survey on June, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- C-13) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor; Balsam 10-N54E-56, Spruce 10-N57½W-37
- C-13) 1892 and Beuthien Survey; Cedar stake and iron kettle, Corner fence post-N44½W-54, Telephone Pole-N48E-51
- 1910
- C-13) 1893 County Surveyor; No description or witnesses provided.
- C-13) 1898 Beuthien Survey; Stake and blue stone dipped in top. Cedar Fence Post 7-N87E-30, Telephone Pole 10-N56W-33.
- C-13) 1907 County Surveyor; Cedar stake
- C-13) 1978 Wilcox LCRC, Liber 1, Page 532; Found 3/4" iron rod and raised with 1/2" iron, Power Pole-S30W-73.82, Cottonwood 8-S75W-64.71, corner is 2.5' north of fence to west and in Centerline N-S road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-13) Section Corner common to Sections 31 and 32, T22N, R6W and Sections 5 and 6, T21N, R6W; Found Iron and cap. Corner is in Centerline of N-S road. No evidence of County Surveyor Witnesses or monumentation. This corner is accepted as the best available evidence of the original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-13) Set Missaukee County Monument on existing Iron in monument box
 - S75W 71.93 12" Willow
 - S42W 50.48 6" Elm
 - S40W 73.85 Power Pole
 - N7W 80.46 Corner Fence Post

Peer Group Reviewed and Approved
Date: 10-21-98
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____

Date 11-2-98

Surveyor's Michigan License No. 33957

