

SURVEY & REMONUMENTATION

JAN 27 1999

LIBER 323 PAGE 1234

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

1285

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>06W</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED NOV 13 1998 9:50 AM

Carolyn Flors
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, J. Dean Geers, P.S., in a field survey on June, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

- E-13) 1837 GLO Section Post by John Brink, Deputy Surveyor; Hemlock 14-N60½W-15, Hemlock 22-N35E-46
- E-13) 1893 County Surveyor; Corner was used but no description or witnesses provided

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-13) Section Corner common to Sections 32 and 33, T22N, R6W and Sections 4 and 5, T21N, R6W; Found pk nail as established by Dan Schripsema. The Corner is in the Centerline of N-S road and in Centerline of road to east and in field line to the west. This Corner is accepted as the best available evidence of the position of the original Corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-13) Set 1/2" x 18" Rebar with Missaukee County Monument in Monument Box

S50E	51.29	8" Elm, Found nail
S82E	155.53	12" Elm, Found nail
N81E	90.64	7" Cherry, Found nail
N07W	116.50	3" Apple
N75E	53.82	12" CMP, Set PK nail

Peer Group Reviewed and Approved

Date: 10-8-98
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative



Signed by _____
Surveyor's Michigan License No. 38977

Date 11-2-98