

SURVEY &
REMONUMENTATION

JAN 27 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 303 PAGE 1235

1286

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>06W</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED NOV 13 1998 9:50
P.M.

Carolyn Flare
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, J. Dean Geers, P.S., in a field survey on June, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-13) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor; Beech 8-N49E-38, Sugar 14-N16W-11

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13) Quarter Section Corner common to Section 33, T22N, R6W and Section 4, T21N, R6W; Found iron and cap established by Dan Schripsema. The Corner is in the Centerline of road to west, ±10' west of Centerline road to north and ±3' south of fence line to east. This corner is accepted as the best available evidence of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13) Set Missaukee County Monument on existing Iron

N50E	41.61	Fence Post, Found nail
N29E	75.72	Fence Post, Found nail
S86W	97.55	10" Twin Elm, Found nail
N58W	61.57	North end 15' CMP, Set PK nail

Peer Group Reviewed and Approved

Date: 10-2-98
J. Dean Geers, Missaukee Co. Representative



Signed by _____
Surveyor's Michigan License No. 33977

Date 11-2-98