

**SURVEY &  
REMONUMENTATION**

JAN 27 1999

LIBER 323 PAGE 1237

# 1288

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>06W</u>	<u>H-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN  
RECORDED NOV 13 1998 950  
RM  
*Carolyn Flare*  
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, J. Dean Geers, P.S., in a field survey on June, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor; Hemlock 10-N34 1/2 E-41, Hemlock 11-N40W-20

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13) Quarter Section Corner common to Section 34, T22N, R6W and Section 3, T21N, R6W; Found iron and cap as established by Dan Schripsema. The Corner is ±25' west of two-track and ±43' west of N-S fenceline. This Corner is accepted as the best available evidence of the position of the original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13) Set Missaukee County Monument on existing Iron  
 S23E 88.12 Fence Post, Found Spike  
 S65E 44.45 Fence Post, Found Spike  
 N45E 66.77 Fence Post, Found Spike  
 N58E 59.90 48" Maple Stump

Peer Group Reviewed and Approved

Date: 10-21-98

*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by \_\_\_\_\_

Date 11-2-98

Surveyor's Michigan License No. 33977

