

**SURVEY &
REMONUMENTATION**

JAN 27 1999

LIBER 323 PAGE 1239

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

1290

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>06W</u>	<u>J-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED NOV 13 1998

9:50
A.M.

Paulyn Klare
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, J. Dean Geers, P.S., in a field survey on June, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- J-13) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor; Hemlock 14-N63 1/2 E-30, White Pine 16-N49 1/2 W-40
- J-13) 1981 Wilcox LCRC, Liber 1, Page 645, Set Rerod by single proportion, Balsam 2-S60W-14.45, Poplar 8-N35E-18.59, Maple 5-S72E-27.82, Maple 4-S06W-26.99
- J-13) 1987 DNR LCRC, Found 1/2" Rod set by Wilcox, Poplar 10-N35E-18.59, Sugar Plum 5-S72E-27.82, Maple 6-S06W-26.99, Balsam 2-S60W-14.45, Maple 4-S25W-26.69

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-13) Quarter Section Corner common to Section 35, T22N, R6W and Section 2, T21N, R6W; Found Iron and Cap as recorded in Liber 1, Page 645. This Corner is accepted as the best available evidence of the position of the original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-13) Set Missaukee County Monument on existing Iron
 - N35E 18.6 10" Poplar, Dead, No nail
 - S72E 27.89 5" Sugar Plum, Found Nail
 - S06W 27.05 10" Maple, Found nail
 - S60W 14.48 6" Balsam Fir, Found Nail
 - S25W 26.80 6" Maple, Found nail
 - S45E 8.00 3" maple


Peer Group Reviewed and Approved

Date: 10-21-98

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____

Surveyor's Michigan License No. 33977



Date 11-2-98