

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

# 1206

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 6W	M-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 315 PAGE 1108  
 MISSAUKEE COUNTY MICHIGAN  
 RECORDED DEC 29 1997 <sup>1:25</sup> P.M.  
*Carolyn Flare*  
 REGISTER  
 Register of Deeds Stamp & File Number

I, Daniel E. Schripsema, in a field survey on October 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

A. Description of original monument and accessories and/or subsequent restoration:

M-2) 1837 John Brink GLO survey set quarter post section 1; Lym 12 S61W 11, Hemlock 10 N64 1/2W 29  
 1914 Beuthien survey, FB #34, pg. 53, set cedar stake, Poplar 6 N08W 70, Cedar Fence Post East 19 1/2 feet,  
 Tamarack 5 N69E 38

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2) Corner common to Section 1, T22N, R6W and Section 6, T22N, R5W. Found 1/2" rod and cap #25850 at fence corner.

This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


M-2) Set Missaukee County Monument on existing iron

- N16E 9.23' 4" Elm
- N83W 9.52' East Gate Post -Fd. Nail
- S08W 29.07' 8" Poplar
- North 0.38' Corner fence post

Peer Group Reviewed and Approved  
 Date: 12/15/97  
*J. Deen Geers*  
 J. Deen Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema* Date 12-2-97

Surveyor's Michigan License No. 24617



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT., 1995

**SURVEY &  
 REMONUMENTATION**

JAN 16 1998

SECTION