

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>6W</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1207

LIBER 315 PAGE 1109

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 29 1997 ^{1:35} P.M.

Carolyn Flare
 REGISTER
 Register of Deeds Stamp & File Number

I, Daniel E. Schripsema, in a field survey on October 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- M-3) 1837 John Brink GLO survey set post section 1 & 12; Hemlock 14 S83 1/2W 47, do 10 N14W 19
- 1913 Beuthien survey, FB #11, pg.77, old cor. Good, iron stake & stone
- 1914 Beuthien survey, FB #18, pg.79, iron stake and stone
- 1914 Beuthien survey, FB #34, pg.53, iron stake and stone in center of highway
- 1995 Daniel E. Schripsema survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-3) Corner common to Section 1& 12, T22N, R6W and Section 6 & 7, T22N, R5W. Found 1/2" rebar in centerline of intersection.

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-3) Set Missaukee County Monument on existing 1/2" iron

- S36W 47.82' P. Pole Fd. nail
- S14 E 269.64' P. Pole
- S52E 61.71' Telephone Ped. Post
- N22W 43.11' sign post

Peer Group Reviewed and Approved

Date: 12-18-97
J. Dean Beers
 J. Dean Beers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema* Date 12-2-97

Surveyor's Michigan License No. 24617



SURVEY & REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995

JAN 16 1998

SECTION