

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

#1210

For corners in

Missaukee <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 22N R 6W	M-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 315 PAGE 1112  
 MISSAUKEE COUNTY MICHIGAN  
 RECORDED DEC 29 1997 <sup>1:25</sup> PM  
*Paulyn Flare*  
 REGISTER  
 Register of Deeds Stamp & File  
 Number

I, Daniel E. Schripsema, in a field survey on October 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

A. Description of original monument and accessories and/or subsequent restoration:

M-6) 1837 John Brink GLO survey set quarter post for section 13; Beech 10 S41W 4, do 10 N21 1/2W 30  
 1899 Richardson survey, WP stub 40 S70E 90  
 1980 Ostling survey, DNR Plan No. R-57-C, found 1/2" iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6) Corner common to Sections 13, T22N, R6W and Section 8, T22N, R5W. Found 1/2" iron at 7' West of N & S road centerline an 11' North of pasture fence to East.

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6) Set Missaukee County Monument on existing 1/2" rebar

- S33W 23.50' 5" Basswood in clump
- S70E 43.12' North gate post
- N66W 38.76' P. Pole
- N46E 38.76' 8" Elm
- S73E 42.58' Fence corner

Peer Group Reviewed and Approved  
 Date: 12-18-97  
*J. Dean Ebers*  
 J. Dean Ebers, Missaukee Co. Representative

Signed by: *Daniel E. Schripsema* Date 12-2-97

Surveyor's Michigan License No. 24617



**SURVEY &  
 REMONUMENTATION**

JAN 16 1998

SECTION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT., 1995