

MAY 28 1997

LIBER 308 PAGE 706

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1075

For corners in <u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>6W</u>	<u>M-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN
 RECORDED **DEC 20 1996** *9:45 AM*
Carolyn Klare
 REGISTER
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Dean Geers, in a field survey on December, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-8) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor; Beech 8-S31 1/2W-20; Beech 10-N43 1/2W-37
- M-8) 1898 Co. Survey in Section 19, T22N, R5W; WPS 40-N88W-66
- M-8) 1913 Beuthien Survey in Section 19, T22N, R6W; WPS 40-N88W-66
- M-8) 1980 DNR Survey in Section 24, T22N, R6W, Proj No 02-5562; Found 2" Iron Bolt

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-8) Corner Common to Section 24, T22N, R6W and Section 19, T22N, R5W; Reset Iron per DNR Survey. Corner is ±3' North of fence line to the East and ±2' East of centerline road North-South. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-8) Set 1/2" Iron and Miss. Co. Mon.
 N57E - 34.49 - 16" Maple
 S75E - 38.10 - 10" Oak
 S45W - 34.39 - 5" Poplar
 N55W - 44.24 - Fence Post

Peer Group Reviewed and Approved
 Date: 12-19-96
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

Signed by _____ Date 12-19-96

Surveyor's Michigan License No. 33977

