

MAY 28 1997

LIBER 308 PAGE 707

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Missaukee (County) Located In: Corner Code #
1. Public Land Survey T 22N R 6W M-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. , Recorded Plat
5. Private Claims

1076 MISSAUKEE COUNTY MICHIGAN RECORDED DEC 20 1996 9:45 A.M. Register of Deeds Stamp & File Number

I, J. Dean Geers, in a field survey on , 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is present at the intersection of column M and row 9.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-9) 1837 GLO Section Post by John Brink, Deputy Surveyor, Lynn 16-N53W-17; Birch 12-N71 1/2W-17
M-9) 1898 Co. Survey in Section 19, T22N, R5W; No Wit's
M-9) 1913 Beuthien Survey in Section 19, T22N, R5W; No Wit's
M-9) 1980 DNR Survey in Section 24, T22N, R6W, Proj. No 02-5562; Found 5/8" Iron rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-9) Corner Common to Sections 24 and 25, T22N, R6W and Sections 19 and 30, T22N, R5W; Found 5/8" Iron of record in Centerline Intersection. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9) Set Missaukee Co. Mon. on 1/2" Iron in mon. box
S45W - 41.93 - Corner Fence Post
S35E - 39.47 - Corner Fence Post
S60E - 68.43 - Fence Post
N45E - 48.39 - Fence Post by Tel. pedestal

Peer Group Reviewed and Approved Date: 12-19-96 J. Dean Geers, Missaukee Co. Representative

Signed by Date 12-19-96

