

MAY 28 1997

LIBER 308 PAGE 709

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1078

For corners in MISSAUCKEE
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 22N R 6W M-11
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

MISSAUCKEE COUNTY MICHIGAN

RECORDED DEC 20 1996 9:45 A.M.

Carolyn Klare
REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|----|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | 12 |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | 25 |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | 24 |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | 35 |
| 13 | | | | | | | | | | | | | |

I, J. Dean Geers, in a field survey on December, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-11) 1837 GLO Section Post by John Brink, Deputy Surveyor; Cedar 8-S60W-12; Tamarack 9-N19W-11
- M-11) 1977 Cavanagh Survey in Section 31, T22N, R5W; Set 1/2" Steel Bar, 16" Poplar-North-26.0; 6" Poplar-S75W-19.3; 12" Poplar-S60E-14.6
- M-11) 1979 Cavanagh LCRC, Liber 1, pg 543; Recorded corner per 1977 Survey, 16" Poplar-North-26.0; 6" Poplar-S75W-19.3; 12" Poplar-S60E-14.6

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-11) Corner Common to Sections 25 and 36, T22N, R6W and Sections 30 and 31, T22N, R5W; Found Iron as recorded in LCRC, Liber 1, Page 543. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-11) Set Miss. Co. Mon. on existing Iron
 - N10E - 26.74 - 16" Poplar, Fd. Blaze
 - S60E - 14.97 - 12" Poplar, Fd. Blaze
 - N45E - 15.86 - 4" Ash
 - S62W - 23.32 - 8" Poplar
 - N10W - 14.53 - 3" Ash

Peer Group Reviewed and Approved

Date: 12-19-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____
Surveyor's Michigan License No. 33977



Date 12-19-96