

MAY 28 1997

LIBER 308 PAGE 710

1079

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in Missaukee
(County)

Located In:

Corner Code #

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 20 1996 9:45 A.M.

Carolyn Flare
REGISTER

Register of Deeds Stamp & File Number

1. Public Land Survey	T	<u>22N</u>	R	<u>6W</u>	<u>M-12</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling In Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, J. Dean Geers, in a field survey on December, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- M-12) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor; B. Ash 10-S28 1/2W-19; Cedar 11-N23W-10
- M-12) 1979 Cavanagh Survey in Section 31, T22N, R5W; Unrecorded, Set 1/2" steel bar, 4" Ash-South-30.25, 4" Ash-N 80E-33.5, 4" Ash-N35E-55.35

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-12) Corner Common to Section 36, T22N, R6W and section 31, T22N, R5W; Found Iron as set by Larry Cavanagh. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-12) Raised Iron with 1/2" Iron and Miss. Co. Mon.

- N83E - 33.10 - 8" Ash, Fd. Blaze
- N50W - 33.52 - 4" Ash
- S20E - 20.09 - 6" Ash
- N65W - 55.95 - 8" Ash

Peer Group Reviewed and Approved

Date: 12-19-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____

Date 12-19-96

Surveyor's Michigan License No. 3397

