

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 308 PAGE 704

1073

For corners in Missaukee (County) Located In: Corner Code #

1. Public Land Survey	T	<u>22N</u>	R	<u>6W</u>	<u>M-13</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Section	S		T		
	S		T		

MISSAUKEE COUNTY MICHIGAN
 RECORDED **DEC 20 1996** 9:45 A.M.
Ruby Flare
 REGISTER
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, J. Dean Geers, in a field survey on December, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-13) 1837 GLO Section Post by John Brink, Deputy Surveyor; Beech 10-N68E-11; Beech 10-N50 1/2W-55
- M-13) County Survey Notes; Iron Post, Beech 10-N68E-11; Beech 10-N50 1/2W-55; Beech 6-S49W-84
- M-13) 1981 Wilcox LCRC, Liber 1, pg 645; Found 5/8" Iron; Due South-33.71-Corner Fence Post; N75W-17.70-12" Poplar; Due North-44.85-Corner Fence Post; N40E-53.33-Fence Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-13) Section Corner Common to Section 36, T22N, R6W, Section 31, T22N, R5W, Section 6, T21N, R5W, and Section 1, T21N, R6W; Found 5/8" Iron of Record. This Corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-13) Set Missaukee Co. Mon. on existing Iron
 N05E-44.93-Corner Fence Post, Fd. nail
 S40W-39.88-6" Tri. Cherry
 S40E-47.23 - 4" Cherry
 N33E-48.05 3" Twin Oak

Peer Group Reviewed and Approved
 Date: 12-19-96
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

Signed by _____ Date 12-19-96
 Surveyor's Michigan License No. 3397

