

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 22 N.R. 8 W


MISSAUKEE COUNTY

DESCRIPTION OF CORNER 1/4 Corner Common to Sections 26 - 27

CORNER MONUMENT Set Std. Dept. Mon. buried in N-S Direct Road

DATE MONUMENT PLACED AND WITNESSED OCTOBER 1968

WITNESSES TO CORNER.....



NO WITNESSES AVAILABLE

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by single proportion from County Survey of Record of sections 26 & 27, dated April 1917. Distance South to Found square head bolt is 2618.2 ft. Measured. Distance North to found 3/4" pipe is 2609.8 ft. measured. There is a P.I. in the M-55 road alignment, being a boat spike, which is 2.52 feet West of the SE corner of Sec. 27.

SURVEYOR'S SEAL

SIGNED Carl F. Roser DATE 1/19/69
REGISTERED LAND SURVEYOR #12028