

OCT 24 2000

1092

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 308 PAGE 885

For corners in

<u>Missaukee County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 22N R 8W</u>	<u>C-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

MISSAUKEE COUNTY MICHIGAN
RECORDED DEC 30 1996 4:30 P.M.
Carolyn Klare
REGISTRAR
Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- C-13) 1837 GLO by John Brink, Deputy Surveyor - set corner Sections 31 & 32, Hemlock 16" N22E 40, Yellow pine 16" N37W 13
- 1941 Frank McClung survey, stake - Power Pole N23 1/2E 37', 15" Oak S72E 72.2', Tel. Pole S31E 25.1'
- 1967 MDOT Witness form - Carl F. Roser, LCRC No. 226. Set 7/8" dia. Side-rail pin, (2' long & 0.5' deep).
Power pole N25E 37.11', Telephone pole S05E 22.46', Corner fence post Due South 48',
21" White pine stump S25W 90.44', W. end of guard post S70E 23.74', ctr. 20' wide. Bit. Rd. Due N. 12'
- 1974 Jerry L. Wilcox LCRC No. 65, fd. 7/8" side rail pin
- 1975 Jerry L. Wilcox LCRC No. 185, fd. 7/8" iron
- 1978 Jerry L. Wilcox survey, S1, pg. 397
- 1985 Jerry L. Wilcox survey, S2, pg. 237
- 1989 J. L. Wilcox & Assoc., Inc. survey, S2, pg. 533
- MDOT right of way map, proj. 57-6, control section 57021, sheet 32
- MDOT right of way map, proj. 57-6, control section 57023, sheet 13

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Section corner common to Sections 31 & 32, T22N, R8W, and Sections 5 & 6, T21N, R8W, found 7/8" dia. Side rail pin.
This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-13) Set Miss. Co. remonumentation Cap on existing iron
- S16W 50.59' 10" beech
- S22E 58.37' 14" beech
- N22E 37.82' power pole
- N23W 63.91' 10" maple in clump
- N04E 12.96' 1/2" iron in mon. box 1' north of centerline of E&W road

Peer Group Reviewed and Approved

Date: 12-30-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____ Date 12-30-96

Surveyor's Michigan License No. 24617

