

Survey & RECONSTRUCTION

OCT 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1094

LIBER 308 PAGE 887

For corners in

<u>Missaukee County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>8W</u>	<u>E-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN
 RECORDED DEC 30 1996 4:30 P.M.
Carolyn Klare
 REGISTER
 Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

- A. Description of original monument and accessories and/or subsequent restoration:
- E-13) 1837 GLO by John Brink, Deputy Surveyor - Set post corner Sections 32 & 33, Beech 11" N82 1/2 E 60, Beech 11" N31 1/2 W 51 1909 County Surveyor notes pg. 66, Sec. 33, T22N, R8W, stake - Pine 30" N46W 62, telephone pole N61E 79, pine s(uprooted) N56 1/2 E 72 1/2
 - 1941 Frank McClung survey, stake - Tel. pole N31E 62.6', Power pole N43 1/2 W 39', Tel. pole S32 1/2 W 31.6'
 - 1966 MDOT corner witness, C. F. Roser, LCRC No. 225, Found wood stake, raised with 3/4" pipe.
 - NW. cor. Conc. Fdn (gar. Attached to hse) S20E 154.33, Ctr. Bit. Rd. North Due East 2', Ctr. Bit. Rd. E&W Due South 4', Power pole N45W 40.93', Telephone pole S35W 32.90', NE cor. Conc. Fdn. (porch attached to hse) S40E 152.14'
 - 1975 LCRC No. 185, J. L. Wilcox and Assoc., Inc. fd. 3/4" pipe
 - 1978 J. L. Wilcox and Assoc., Inc. survey - S1, pg. 397
 - 1978 J. L. Wilcox and Assoc., Inc. survey - S1, pg. 421
 - 1979 J. L. Wilcox and Assoc., Inc. survey - S1, pg. 513
 - 1993 Daniel E. Schripsema survey - S3, pg. 192-194
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- E-13) Section Corner common to Sections 32 & 33, T22N, R8W and Sections 4 & 5, T21N, R8W, Found 3/4" pipe of record, 4' north of centerline road and 2' west of centerline road north. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- E-13) Set Miss. Co. remonumentation. Cap on existing iron
 - S33W 51.66' utility pole (fd. Nail)
 - N46W 41.21' power pole stub (fd. Nail)
 - S76E 113.54' power pole (fd. Nail)
 - S14W 28.38' pk nail in west end culv.

Peer Group Reviewed and Approved
 Date: 12-30-96
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

Signed by Daniel E. Schripsema
 DANIEL E. SCHRIPSEMA
 Surveyor's Michigan License No. 24617
 SURVEYOR
 No. 24617
 REGISTERED LAND SURVEYOR

Date 12-30-96