

OCT 24 2000

1100

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 308 PAGE 893

For corners in

<u>Missaukee County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 22N R 8W</u>	<u>K-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

MISSAUKEE COUNTY MICHIGAN

RECORDED **DEC 30 1996** 4:30 P.M.

Carolyn Klare
REGISTER
Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

K-13) 1837 GLO survey by John Brink, Deputy Surveyor, set post - Cedar 10° N20 1/2 E 10, Cedar 10° N29W 17
1956 Frank McClung survey, pg. 72 county surveyor notes
1992 Matthew M. McClung survey, Found stove damper with point upright, set 5/8" iron rod w/cap, 8" maple East 1.00',
14" Cedar NE 28.83, 10" ash North 26.90', 12" cedar SSE 32.68'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13) Section corner common to Sections 35 & 36, T22N, R8W, and Sections 1 & 2, T21N, R8W, Found 5/8" iron rod w/cap. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Miss. Co. remonumentation cap on existing iron.
S85E 1.52' 8" Maple
N62E 28.77' 14" Cedar (Fd Nail)
N05E 26.86' 10" Ash (Fd Nail)
S20E 32.63' 12" Cedar (Fd Nail)
East 32.60' 4" x 36" pipe

Peer Group Reviewed and Approved

Date: 12-30-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by Daniel E. Schripsema Date 12-30-96

