

SURVEY &
REMONUMENTATION

MAY 28 1987

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#1097

LIBER 308 PAGE 890

For corners in

Missaukee County (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>8W</u>	<u>H-13</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

MISSAUKEE COUNTY MICHIGAN
RECORDED **DEC 30 1996** 4:30 P.M.
Carolyn Klare
REGISTRAR
Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-13) 1837 GLO survey by John Brink, Deputy Surveyor, set post - Maple 11" N29 1/2 E 28, Hemlock 10" N48W 04
1912 County survey records, land side of plow - Tel. pole S66E 100
1974 J. L. Wilcox and Assoc., Inc., LCRC No. 166, Set 1/2" rod on line between found corners, prop.
Distance on township line - 0.25' N. of centerline, North Power pole 52.97', S40E Telephone pole 103.35'
1974 J. L. Wilcox and Assoc., Inc. survey S1, pg. 167
1979 MDOT right of way map, file no. 57-R-2, project 57-6, control section 57021, sheet 32

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13) Section corner common to Section 34, T22N, R8W and Section 3, T21N, R8W, Found 1/2" rod 0.25' north of centerline.
This corner is accepted as a careful and faithful re-establishment of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Miss. Co. remonumentation cap on existing iron
N03W 53.01' Power Pole (Fd Nail)
N01W 116.43' 6" Cherry
N35E 60.39' Set 1/2" Iron
S23W 48.89' Set 1/2" Iron
S01W 58.33' Center Fence Post

Peer Group Reviewed and Approved
Date: 12-30-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by Daniel E. Schripsema Date 12-30-96

