

**SURVEY & REMONUMENTATION**

MAY 28 1997

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

#1098

LIBER 308 PAGE 891

For corners in

<u>Missaukee County</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>8W</u>	<u>I-13</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN  
 RECORDED **DEC 30 1996** <sup>4:30</sup> P.M.  
*Caryn Klare*  
 Register of Deeds Stamp  
 Number

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- I-13) 1837 GLO survey by John Brink, Deputy Surveyor, set post - hemlock 10 N27E 15, Hemlock 11 N77W 34
- 1912 County Surveyor notes- stone - cedar fence post 12 S3W 49
- 1956 Frank McClung survey - shown with no witnesses or description
- 1966 MDOT corner wit. - C. F. Roser, LCRC No. 216, Fd. Remains of old bolt, re-set 1" pipe, 18' maple N20E 121.36', power pole N50E 41.73', telephone pole S70E 129.84', ctr. E-W bit. rd. due south 2'
- 1974 LCRC No. 166, J. L. Wilcox and Assoc., Inc., fd. iron in mon. box, - North tel. Pole 36.43', N45E P. pole 41.72', 2.4' N. of centerline
- 1979 MDOT right of way map, file No. 57-R-2, proj. 57-6, control section 57021, sheet 32


**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- I-13) Section corner common to sections 34&35, T22N R8W and sections 2&3, T21N R8W. Found 1" pipe 2.5' North of centerline Cadillac Rd and in centerline road north. This corner is accepted as a careful and perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Set Miss. Co. remonumentation cap on existing pipe
- N47E 41.64' Power Pole ( Fd Nail )
- N15E 121.42' 26" Maple ( Fd Nail )
- N38W 78.08' 5" Elm ( Fd Nail )
- N71W 161.05' Power Pole ( Fd Nail )
- S05W 34.09' Phone Riser
- South 32.70' End Fence Post

Peer Group Reviewed and Approved  
 Date: 12-30-96  
*J. Dean Geers*  
 J. Dean Geers, Missaukee Co. Representative



Date 12-30-96