

**SURVEY &  
REMONUMENTATION**

MAY 28 1997

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

# 1099

LIBER 308 PAGE 892

**COMMISSION**

For corners in

<u>Missaukee County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>8W</u>	<u>J-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN

RECORDED **DEC 30 1996** 4:30 PM

*Carolyn Klare*  
REGISTRAR  
Register of Deeds Stamp & File  
Number

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11			
5												
6	18		17		16		15		14			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

**A. Description of original monument and accessories and/or subsequent restoration:**

- J-13) 1837 GLO survey by John Brink - set post - Beech 14, N22E, 32, Hemlock 10 N40W 20
- 1914 survey in County Survey records, shown but not identified, wit. - cor. fe. Post S39 1/2 E 54, cor. fe. Post N 1 E 50.
- 1956 Frank McClung survey, 1" pipe at intersection of roads
- 1992 Matthew McClung survey, fd. 1" pipe / set iron and cap - 12" Aspen S20W 19.04', 8" cedar fence post N15W 34.75', tel. Riser box N55E 53.1', 10" Aspen S55E 33.1'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- J-13) Quarter Section corner common to section 35 T22N, R8W, and section 2 T21N, R8W. Found 5/8" Iron & Cap #13037, 4' South centerline gravel road. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established perpetuate locating the position of the corner:**

- Set Miss. Co. remonumentation cap on existing iron.
- S56E 33.19' 12" Aspen ( Fd Nail )
- S32W 19.06' 12" Aspen ( Fd Nail )
- N59E 52.36' Phone Riser ( Bent )
- N04E 32.99' Fd 1/2" Iron
- N11W 34.67' 8" Post (Fd Nail )
- N68W 93.76' 26" Maple (Fd Nail )

Peer Group Reviewed and Approved

Date: 12-30-96  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

