

# SURVEY & REMONUMENTATION

MAY 28 1997

## COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

# 1101

LIBER 308 PAGE 894

For corners in

<u>Missaukee County</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>8W</u>	<u>L-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 30 1996 <sup>4:30</sup> <sub>PM</sub>

*Carolee Florie*  
Register of Deeds Stamp & File Number REGISTER

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

L-13) 1837 GLO survey by John Brink, Deputy Surveyor - called for a cedar 10" dia. Quarter section corner, no witnesses were given 1992 Matthew McClung, Set 5/8" rod & cap on line and equal distance, wit. 11" twin cedar N85W 2.85', 8" cedar S85E 7.40', E & W barbed wire fence South 30.0', 10" cedar N85W 15.0'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-13) Quarter Section corner common to Section 36, T22N, R8W and Section 1, T21N, R7W. Found 5/8" rod and cap. This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-13) Replaced 5/8" rod with 5/8" x 36" rod and set Missaukee County Remonumentation Cap

S50E 7.88' 10" cedar (fd. Nail)  
N48W 16.63' 12" cedar (fd. Nail)  
S51W 42.23' 5" balsam  
S82W 33.47' 6" cedar

Peer Group Reviewed and Approved

Date: 12-30-96  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by Daniel E. Schripsema Date 12-30-96

Surveyor's Michigan License No. \_\_\_\_\_

