

SURVEY & REMONUMENTATION

LIBER 291 PAGE 422

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

971

For corners in
Missaukee **COMMISSION**
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>22N</u> R <u>8W</u> | <u>M-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

MISSAUKEE COUNTY MICHIGAN

RECORDED **NOV 23 1995** 11/27 LL/AN

Rosalyn Flare
 REGISTER
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, J. Dean Geers, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- M-9) 1837 GLO post by John Brink, Deputy Surveyor
 Beech 10 S 57 1/2' W 65, Hemlock 121 N 69 1/2' W 21
 - M-9) 1894 Beuthien surveys: Iron and stone, fence post Southwest 53', tele pole Northwest 59', East end culvert S 20 1/2' E 38 1/2'
 - M-9) 1907 Beuthien survey: King bolt 1" x 16" long
 - M-9) 1910 & 1911 Beuthien survey: 2" well pipe in center of highway, East end culvert S 20 1/2' E 38 1/2'
 - M-9) 1939 MDOT Plans, Project #57-6, File #S-20-C-3A: Iron stake with witnesses
 - M-9) 1978 Wilcox LCRC, Liber 1, page 538: Set railroad spike from 1939 MDOT witnesses
 - M-9) 1978 Wilcox surveys, Liber S-1, page 419 & 444: found railroad spike per Liber 1, page 538

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- M-9) Section corner common to Section 24 & 25, T22N, R8W and Section 19 & 30, T22N, R7W.

Found railroad spike recorded in Liber 1, page 538 in center of intersection. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- M-9) Set 2 1/2" brass Missaukee County monument on 1/2" Iron in monument box

- N 49° W - 66.04 - Set nail in pole at tele riser
- S 34° W - 103.18 - Set nail in pole at tele riser
- N 62° E - 57.48 - Found nail in power pole
- S 63° E - 75.30 - Set nail in corner fence post

Peer Group Reviewed and Approved
 Date: 12-7-94
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/15/94
 Surveyor's Michigan License No. 33977