

**SURVEY &  
REMONUMENTATION**

**LIBER 291 PAGE 421**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

970

APR 24 1995

For corners in

Missaukee **COMMISSION**  
(County)

Located In:

Corner Code #

- |                                    |                          |             |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey              | T <u>22N</u> R <u>8W</u> | <u>M-10</u> |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |

MISSAUKEE COUNTY MICHIGAN

RECORDED **JAN 23 1995** <sup>42</sup> *LAU*

*Paulyn Flare*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	

I, J. Dean Geers, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- M-10) 1837 GLO Quarter Section post by John Brink, Deputy Surveyor  
Beech 10 S 18° W 67, Lynn 7 N 53° W 35
- M-10) 1894 Beuthien survey: Cast iron sleigh shoe 2 1/2" x 1 1/4" x 32" long
- M-10) 1911 Beithien survey: Found cast iron sleigh shoe
- M-10) 1928 MDOT Plans, Project #057-16, File #J-17-A-6: No corner indicated
- M-10) 1978 Wilcox LCRC, Liber 1, page 540: Set Iron from highway ties
- M-10) 1978 Wilcox survey, Liber S-1, page 434 & 435: Found Iron per Liber 1, page 540
- M-10) 1982 Wilcox survey, Liber S-2, page 98: Found Iron per Liber 1, page 540
- M-10) 1985 Wilcox survey, Liber S-2, page 231 & 255: Found Iron per Liber 1, page 540

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10) Quarter Section corner common to Section 25, T22, R8W and Section 30, T22N, R7W

Found Iron and cap recorded in Liber 1, page 540. Corner is in Centerline of North-South road and ± 16' North of Centerline of road to East. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10) Set 2 1/2" brass Missaukee County monument on existing 1/2" Iron in monument box

- S 67° W - 58.62 - Set nail in corner fence post
- N 43° W - 66.81 - Set nail in power pole
- S 84° E - 95.82 - Set nail in twin 4" Spruce
- S 30° E - 49.03 - Set nail in marker post

Peer Group Reviewed and Approved

Date: 12-7-94  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/15/94  
Surveyor's Michigan License No. 33977