

**SURVEY &
REMONUMENTATION**

LIBER 291 PAGE 419

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

969

For corners in **COMMISSION**

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>8W</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN
RECORDED **JAN 23 1995** ⁴¹ *H.A.M.*
Paulyn Flare
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, J. Dean Geers, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-11) 1837 GLO post by John Brink, Deputy Surveyor,
Black Ash 12 N 36° W 58, Black Ash 13 S 33 1/2° W 42
- M-11) 1894 Beuthien survey: Cedar stake and stone; West end culvert S 35° W 32.7'
- M-11) 1911 Beuthien survey: Cedar stake and stone; West end culvert N 44° W 51
- M-11) 1966 MDOT LCRC, Liber 1, page 235: Found 3/4" pipe, raised with 5/8" lag bolt, corner fits 1920, 1935 & 1938 MDOT survey notes
- M-11) 1976 McClung LCRC, Liber 1, page 515: Found 1" Iron in monument box
(continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-11 Section corner common to Sections 25 & 36, T22N, R8W and Sections 30 & 31, T22N, R7W

Found 1" Iron in monument box recorded in Liber 1, page 515. Corner is in center of intersection. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-11) Set 2 1/2" brass Missaukee County monument on 1/2" Iron in monument box

N 43° W - 77.02 - Found nail in power pole
N 48° E - 101.77 - Top center of steel guard post
S 44° E - 58.90 - Found nail in power pole
S 45° W - 58.94 - Set Iron and cap

Peer Group Reviewed and Approved
Date: 12-7-94
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12/15/94
Surveyor's Michigan License No. 33977