

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Missaukee Located In _____ Corner Code # _____
 (County)

1. Public Land Survey		T	<u>22N</u>	R	<u>8W</u>		<u>A9</u>
		T	_____	R	_____		_____
2. Property Controlling in Section	S	T	_____	R	_____		_____
	S	T	_____	R	_____		_____
3. Miscellaneous Property in Section	S	T	_____	R	_____		_____
	S	T	_____	R	_____		_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 14, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| <p><u>A9</u> – GLO – John Brink – 1838
 Beech 9" S15°W 66 L.
 Y. Pine 14" N59°W 21 L.
 - GLO Sub - W. L. Coffinberry – 1853
 Y. Pine 18" S87°E 9 L.
 Y. Pine 22" N30°E 53 L.
 - CSR – Teed – 1905 – L. 1, p. 148
 N. Pine 16" S83½°E 9 L.
 N. Pine 14" N69°W 21 L.
 - L. 2, p. 989 – 1971 – C. F. Roser – fd. 2' piece of metal sign post & remains wood post - 22" Oak N84°E 66.5';
 22" Oak S52°E 109'; 24" Oak S17°E 132.0' Cedar Post w/ loc. tag – East 33'</p> | <p>- Rec. Sur. - L. 1, p. 609 – 1979 – Wilcox – E. 22' Oak 66.5'; S17°E 24" Oak 132.00; S52°E 22" Oak 109.5'
 - Rec. Sur. – L.2., p. 120 – 1984 – James Ray, East 22" Oak 66.5'; S17°E 24" Oak 132.00'; S57°E 22" Oak 109.50'
 - L. 69, p. 664 – Rec. Sur. – Ray – 1990 – DNR Mon. in Mon. Box; N65°E 8" R. Pine 56.10'; N80°E 24: Oak 68'; S20°E stop sign 48.95'; S50°W tele. Ped. 68.00'
 - LCRC – L. 4, p. 194 – Wexford Co. Records – 1993 – R. D. Wilcox – Replaced broken DNR mon with 5/8" x 36" iron and Wexford Co. brass cap stamped SE 24 PS #33989, 1993
 N85°E 68.02' - 22" Oak; S51°E 110.67' - 22" Oak;
 S11°E 133.32' - 24" Oak; N63°E 56.14' - 8" R. Pine</p> |
|--|---|

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A9 – Standard Section Corner common to Sections 19 & 30, T22N, R8W and Sections 24 & 25, T22N, R9W - Fd. Wexford Co. Remon. Brass cap per LCRC L.4, p. 194. Fd. LCRC witnesses OK but dead or dying. Brass cap in mon. box located 2' N. of Centerline bit. rd. West & 7.5' E. of centerline bit. Rd. North. Wexford County Remon. Brass cap accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A9 – Wexford County Brass Remon. Cap on 5/8" x 36" rebar in Mon. Box.
 N32°W 82.96' to set mag N & T in NE side P.P.
 N42°E 101.04' to set N & T in NW side 11" R. Pine
 S68°E 87.33' to set N & T in S. side twin 23" Oak
 S22°W 81.17' to found nail in NW side 10" Cherry in clump of 5.
 Set Blue Carsonite Post with loc. tag N45°E 33'.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/11/2006