

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Missaukee (County)	Located In	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>8W</u>	<u>B8</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 12, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B8 – Unrecorded Survey – LCM Job #032077 –
 William E. Sikkema – 2003 –
 N7°W 29.53' 5" Red Pine
 N79°W 23.06' 5" Maple
 S15°W 8.40' 24" Oak
 N44°E 10.70' 12" Oak

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

B8 – Center ¼, Section 19, T22N, R8W - Found ½" x 18" capped iron rod PS #45505, W.G. Sikkema. Fits intersection of ¼ lines. ½" CIR is accepted as best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B8 – Replaced ½" x 18" CIR w/ stamped 2" Aluminum stamped cap on 5/8" x 34" rebar
 N7°W 29.61' to set N & T at found nail in E. side 8" Red Pine (WES)
 N80°W 22.61' to set N & T at found nail in W. side 5" triple Red Maple (WES)
 S26°W 8.38' to set N & T at found nail in E. side twin 24" Oak (WES)
 N38°E 10.78' to set N & T at found nail in SE side 13" Red Maple (WES)
 Set 1 ¾" O.D. cyclone fence post 1' North
 Set Blue Carsonite post with loc. tag 1' SW.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/11/2006