

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

| | | |
|---|--------------------------|---------------|
| For Corners In: <u>Missaukee</u> (County) | Located In | Corner Code # |
| 1. Public Land Survey | T <u>22N</u> R <u>8W</u> | <u>D8</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Aug. 1, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|---|----|---|----|---|----|---|----|---|----|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| <p><u>D8</u> – 1977 – Rec. Survey L. S-1, p. 306</p> <ul style="list-style-type: none"> - Set 3/4" rod – M. McClung 26" R. Oak N77°20' E 8.40' 18" R. Oak S35°W 41.20' 18" R. Oak S43°E 15.70' Plat mon. N33°24'E 20.28' - 1979 - Rec. Survey - L. S-1, p. 455 – J. L. Wilcox Fd. 3/4" rod. See Survey L. S-1, p. 306 | <ul style="list-style-type: none"> - 1982 – Rec. Survey – L. S-2, p. 111 – John Nelson - Fd. 1/2" iron with RLS Cap #13037 in fence corner N & E. Set nail with tag # 21273 in W. side 28" B. Oak Az. 15° - 9.15; Fd. 3/4" pipe w/ conc. Az. 61° - 20.3'; Set nail with RLS Tag #21273 in NE side 16" B. Oak Az. 143° - 16.29'; Set nail with RLS tag #21273 in E. side 16" B. Oak Az. 220° - 42.06' |
|--|---|

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

D8 – Center 1/4 corner, Section 20, T22N, R8W - Found 5/8" capped iron rod PS #13037 per 1977 Rec. Survey. Fence N & E. 5/8" capped iron rod is accepted as best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D8 – 5/8" capped iron rod PS #13037.

- S41°E 16.28' to found N & T in NE side 20" Oak (MM, JN)
- S36°W 42.16' to set N & T at fd. nail in SE side 22" Oak (MM, JN)
- N30°E 36.56' to set N & T in NE side 20" Oak
- N4°W 10.58' to set N & T in W. side 3" Red Maple
- Set Orange Carsonite Post with Location Tag 1' North



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/11/2006