

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Missaukee Located In _____ Corner Code # _____
(County)

1. Public Land Survey T _____ R _____
T _____ R _____

2. Property Controlling in Section S 19 T 22N R 8W 8
S 19 T 22N R 8W 11

3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 27, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

8 – Rec. Sur. – L. S-2, p. 218 – P. Case – 1985 – Set iron 11 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

8 – CW 1/16, Section 19, T22N, R8W – Fd. ½" capped iron # 14102 – N89°39'W 12.05' from calculated position per Rec. Survey. Didn't accept. Thus set 2" stamped aluminum cap on 5/8" x 34" rebar per Standard BLM procedure.

11 – SW 1/16, Section 19, T22N, R8W. Set 2" Stamped Aluminum cap on 5/8" x 34" rebar per Standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

8 – Stamped 2" Aluminum cap on 5/8" x 34" rebar S19°E 8.60' to set N & T in E. side 7" R. Maple N87°E 45.39' to set N & T in N. side twin 17" R. Maple N17°E 19.46' to set N & T in E. side 8" R. Maple N89°39'W 12.05' to fd. ½" capped iron rod PS #14102 Set Blue Carsonite Post with location tag 1' E.

11 – Stamped 2" Aluminum cap on 5/8" x 34" rebar S12°W 44.56' to set N & T in SE side 4" B. Cherry S74° 50.70' to set N & T in S. side 12" Cedar N54° 15.67' to set N & T in 3" R. Maple N64°E 60.31' to set N & T in 13" Cedar Set Blue Carsonite Post with location tag 1' SE South bank of Clam River North 40'±

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 5/11/2006