

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
Missaukee (County)

1. Public Land Survey	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S <u>20</u>	T <u>22N</u>	R <u>8W</u> <u>8</u>
	S <u>20</u>	T <u>22N</u>	R <u>8W</u> <u>11</u>
3. Miscellaneous Property in Section	S _____	T _____	R _____
	S _____	T _____	R _____

Register of Deeds Stamp & File Number

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Aug. 1, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
8 - 1979 - Rec. Survey - L. S-1, p. 455 - J. L. Wilcox      11 - None  
PS #14102, Set 1/2" iron rod & cap.



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

8 - CW 1/16 Section 20, T22N, R8W - Found 1/2" x 18" capped iron rod per J. L. Wilcox. Barbed wire fence North is 1' West and barbed wire fence West is 1' North. 1/2" capped iron rod is accepted as best available evidence of the position of the corner.  
11 - SW 1/16, Section 20, T22N, R8W. Set 2" stamped aluminum cap on 5/8" x 3/4" rebar per Standard BLM procedure in Tag Elder swamp.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

8 - Replaced 1/2" x 18" capped iron rod with 2" stamped aluminum cap on 5/8" x 3/4" rebar.  
N35°E 30.28' to set N & T in SE side 10" R. Maple in clp. of 4.  
S70°E 18.06' to set N & T in NE side 7" twin R. Maple  
S2°E 51.28' to set N & T in SE side 8" R. Maple in clp. of 3  
S58°W 33.51' to set N & T in SE side 7" R. Maple in clp of 3  
Set Blue Carsonite Post with location tag 1' SW  
11 - 2" Stamped Aluminum cap on 5/8" x 4' rebar.  
S82°W 24.11' to set 1/2" x 18" rebar  
S43°E 25.43' to set 1/2" X 18" rebar  
N58°E 23.74' to set 1/2" X 18" rebar  
N44°W 23.81' to set 1/2" x 18" rebar  
Set Blue Carsonite Post with location tag 1' SE

Signed by: Craig W. McVean  
Surveyor's Michigan License No.: 39088

Date: 5/11/2006