

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 Missaukee (County)

- | | | | | | |
|--------------------------------------|---------|---------|---------|--|---|
| 1. Public Land Survey | | T _____ | R _____ | | |
| | | T _____ | R _____ | | |
| 2. Property Controlling in Section | S 32 | T 22N | R 8W | | 3 |
| | S 32 | T 22N | R 8W | | 4 |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ | | |
| | S _____ | T _____ | R _____ | | |

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____
5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 28, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4			3			2	1
3													
4	7			8		9			10			11	12
5													
6	18			17		16			15			14	13
7													
8	19			20		21			22			23	24
9													
10	30			29		28			27			26	25
11													
12	31			32		33			34			35	36
13													

- A. Description of original monument and accessories and/or subsequent restoration:
3 - None 4 - None



- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- | | |
|---|--|
| <p><u>3</u> - N 1/16 between Sections 31 & 32, T22N, R8W.
 Set 2" Stamped Aluminum cap on 5/8" x 34" rebar per standard BLM procedure. Centerline of N-S 2-track is 2' W.</p> | <p><u>4</u> - NW 1/16, Section 32, T22N, R8W.
 Set 2" Stamped Aluminum cap on 5/8" x 34" rebar per standard BLM procedure.</p> |
|---|--|

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | |
|--|--|
| <p><u>3</u> - 2" Aluminum stamped cap on 5/8" x 34" rebar - down 0.5' below 2-track
 N8°E 83.06' to set N & T in W. side 8" R. Maple clp. of 4
 N80°E 11.61' to set N & T in S. side 6" R. Pine
 N78°W 24.53' to set N & T in S. side 10" R. Pine
 S7°W 109.66' to set N & T in E. side 7" Oak
 Set Blue Carsonite Post with location tag 33' East
 West 2.0'± to Centerline N-S 2-track</p> | <p><u>4</u> - 2" Aluminum stamped cap on 5/8" x 34" rebar
 N64°W 38.24' to set N & T in S. side 4" Oak
 N13°W 29.87' to set N & T in E. side 3" Oak
 S69°E 49.00' to set N & T in S. side 3" W. Pine
 S17°E 32.11' to set N & T in W. side 3" Beech
 Set Blue Carsonite Post with location tag 1' NW</p> |
|--|--|

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/11/2006