

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1105

For corners in

LIBER 308 PAGE 898

<u>Missaukee County</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>7W</u>	<u>E-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED **DEC 30 1996** ^{4:30} _{PM}

Carolyn Flare
Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K
1											
2	6			5		4		3		2	
3											
4	7					9		10		11	
5											
6	18			17		16		15		14	
7											
8	19			20		21		22		23	
9											
10	30			29		28		27		26	
11											
12	31			32		33		34		35	
13											

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

E-13) 1837 GLO survey by John Brink, Deputy Surveyor, set post corner Sections 32 & 33, beech 10' N70W 56, hemlock 10" N51W 28
1899 survey Sec. 5, pg. 62 county surveyor field notes - w. p. roots (body gone) S71W 23
1989 Daniel E. Schripsema LCRC pg. 788, Found R. R. Spike - Yield sign N14E 72.26, 30" Oak S73W 100.56, S. leg rd. sign S88E 14.15, Fence post N54W 130.48, CL Rd. N-S, E-W
1989 Daniel E. Schripsema survey rec. in Liber S-2, pg. 466 & 468
1995 J. Dean Geers survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13) Section corner common to Sections 32 & 33, T22N, R7W, and Sections 4 & 5, T21N, R7W, Found 1/2" iron in old fence line N & S. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Missaukee County Remonumentation cap on existing 1/2" iron

S59E 4.61' 10" Balsam (fd. Nail)
N40W 10.20' 6" Balsam (fd. Nail)
S82W 14.34' 7" Balsam (fd. Nail)
East 34.40' 26" Cherry (fd. Nail)
South 0.32' 1" x 4' pipe

Peer Group Reviewed and Approved

Date: 12-30-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema*
DANIEL E. SCHRIPSEMA
Surveyor's Michigan License No. 24617
SURVEYOR
No. 24617
REGISTERED LAND SURVEYOR

Date 12-30-96