

SURVEY &
REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#1106

LIBER 308 PAGE 899

For corners in

<u>Missaukee County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 7W	F-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

MISSAUKEE COUNTY MICHIGAN
RECORDED: DEC 30 1996 ⁴³ _{PA}
Carolyn Flare
REGISTERED
Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K
1											
2	6			5		4			3		2
3											
4	7			6		5			4		3
5											
6	10			9		8			7		6
7											
8	13			12		11			10		9
9											
10	16			15		14			13		12
11											
12	19			18		17			16		15
13											

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:
F-13) 1837 GLO survey by John Brink, Deputy Surveyor - Quarter section corner in stream and was not set
1989 Daniel E. Schripsema LCRC, pg. 789, Meander corner set - corner falls in cattail swamp in Clam River, set meander cor. or east bank of river - 4" poplar N64E 11.49', 10" poplar N70E 31.93', 4" poplar S68E 23.21', 10" poplar S22E 49.36'
1989 Daniel E. Schripsema survey recorded liber S2, pg. 466 - 468
1995 J. Dean Geers survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
F-13) Quarter corner common to Sections 33, T22N, R7W and Section 4, T21N, R7W. Corner was not set and falls in Clam River. Corner was computed midway and on line between Government Corners East and West. Reference corners were found per 1995 Geers survey, S00-04-50W 128.57', N88-48-58W 300.00' and S88-48-58E 170.14' of the computed corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Witnesses for reference corner bearing S00-04-50W 128.57' from computed 1/4 corner location
Set Missaukee County Remonumentation corner on existing 1/2" iron
S44E 113.60' 14" poplar
S70E 91.28' 14" poplar
N86E 85.18' 14" maple
N62E 122.53 12" maple
Peer Group Reviewed and Approved
Date: 12-30-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by Daniel E. Schripsema
DANIEL E. SCHRIPSEMA
Surveyor's Michigan License No. 24617
SURVEYOR
NO. 24617
MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS

Date 12-30-96