

SURVEY & REMONUMENTATION

OCT 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

#1107

For corners in

<u>Missaukee County</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>7W</u>	<u>G-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

LIBER 308 PAGE 900

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 30 1996 4:30 P.M.

*Paulyn Flare*  
Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

G-13) 1837GLO survey by John Brink, Deputy Surveyor, set post corner - Cedar 11 N37E 28, cedar 10" N29 1/2 W 28  
1900 survey of Sec. 34, pg. 80 of county surveyor field notes - cedar 10" S17 1/2 E 18, cedar 12" S34W 52  
1969 survey by Bill Batzer, showing corner for survey in section 34

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13) Section corner common to Sections 33 & 34, T22N, R7W and Sections 3 & 4, T21N, R7W. Found 3/4" pipe @ intersection of road grade remains/clearing strips. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Missaukee Remonumentation cap on existing iron

N78W 68.42' 14" maple  
N35E 74.58' 9" cherry  
S50W 44.49' 14" tri-maple  
S60E 45.23' 12" maple

Peer Group Reviewed and Approved

Date: 12-30-96

J. Dean Geers, Missaukee Co. Representative

Signed By: Daniel E. Schripsema

Date: 12-30-96

Surveyor's Michigan License No. 24617

