

MAY 28 1987

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1108

LIBER 308 PAGE 901

For corners in

| Missaukee County (County) | Located In: | Corner Code # |
|---------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | T <u>22N</u> R <u>7W</u> | <u>H-13</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 30 1996 4:30 P.M.

Pauline Flare
Register of Deeds State of Michigan
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|---|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | 4 | | 3 | | 2 | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | 9 | | 10 | | 11 | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | | 17 | | 16 | | 15 | | 14 | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | 21 | | 22 | | 23 | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | 28 | | 27 | | 26 | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | 33 | | 34 | | 35 | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

H-13) 1837 GLO survey by John Brink, set post - beech 10" N45 1/2 E 17, sugar 10" N39 1/2 W 55
1900 survey of Sec. 34, T22N, R7W county surveyor field notes
1969 William Batzer survey corner was found, also 1/8 corner East
1985 Granger Engineering, Inc. survey, liber S2, pg. 242, found 3/8" pipe - S02W 24" tri-basswood 14.95', S15E cor. fence p
23.20', S60E 10" cherry 56.55', North S. edge gravel 2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13) Quarter corner common to Section 34, T22N, R7W and Section 3, T21N, R7W. Found 3/8" pipe of record. This corner is accepted careful and faithful perpetuation of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13) Set 1/2" rebar with Missaukee Co. Remonumentation cap
S12E 14.81' 26" tri-basswood 14.81' (fd. Nail)
S08W 23.51' corner fe. post
S60E 56.52' 12" cherry (fd. Nail)
N81E 108.74' power pole
North 13.4' centerline of gravel road
North 2' south edge of gravel road

Peer Group Reviewed and Approved

Date: 12-30-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed Daniel E. Schripsema Date 12-30-96

Surveyor's Michigan License No. 24617

