

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#1109

For corners in

LIBER 308 PAGE 902

<u>Missaukee County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>7W</u>	<u>I-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED **DEC 30 1996** 4:30 P.M.

Carolyn Flare
Register of Deeds State of Michigan
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		18		19		20		21	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- I-13) 1837 GLO survey by John Brink, Deputy Surveyor, set post - beech 10" N61 1/2 E 28, beech 12" N62W 32
- 1900 survey of Sec. 34, T22N, R7W, pg. 80 co. surveyor field notes - cedar fence post 9 S51E 50
- 1911 survey of Sec. 2, T21N, R7W, pg. 84 county surveyor field notes - fence post 10 S51E 50
- 1923 survey of Sec. 35, T22N, R7W, pg. 91 county surveyor field notes - stake - cedar fence post 9 S51E 50 - 33'
- 1957 Rainbow Glen Subdivision, by Maurice M. Buck - corner shown as place of beginning
- 1957 Rainbow Harbor Subdivision, by Maurice M. Buck - corner shown as place of beginning.
- 1979 Jerry L. Wilcox LCRC No. 569, Found R.R. Spike - S70W 71.97' power pole, N50W 33.01' guard post, N45E 56.03' C riser
- 1987 Matthew McClung survey rec. Liber S2, pg. 322

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-13) Section corner common to Section 34 & 35, T22N, R7W and Sections 2 & 3, T21N, R7W - found R. R. spike of record in centerline of intersection
This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-13) Replaced R. R. spike with 1/2" rebar with Miss. Co. mon. cap and monument box
- S66W 71.87' Power Pole (Fd Nail)
- N50W 32.31' Guard Post (Fd Nail)
- N41E 55.89' Phone Riser
- N13W 136.18' 50" Maple
- S78E 136.49' Power Pole

Peer Group Reviewed and Approved

Date: 12-30-96
J. Dear Geers
J. Dear Geers, Missaukee Co. Representative



Signed by Daniel E. Schripsema
Surveyor License No. 24617

Date 12-30-96