

**SURVEY & REMONUMENTATION**

MAY 28 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

# 1110

LIBER 308 PAGE 903

For corners in

<u>Missaukee County</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>7W</u>	<u>J-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED: DEC 30 1996 <sup>4:30</sup> P.M.

*Paulyn Klare*  
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		
3											
4	7		8		9		10		11		
5											
6	18		17		16		15		14		
7											
8	19		20		21		22		23		2
9											
10	30		29		28		27		26		
11											
12	31		32		33		34		35		
13											

A. Description of original monument and accessories and/or subsequent restoration:

- J-13) 1837 GLO survey by John Brink, Deputy Surveyor, set quarter section post - hemlock 11" N59 1/2 E 36, beech 12" N28W 33
- 1911 Beuthien survey of Sec. 2, T21N, R7W, pg.84 of county surveyor field notes - stone - w. p. s. 30° S72E 141
- 1923 survey of Sec. 35, T22N, R7W, pg. 91 county surveyor field notes - stone - w.p.s. S72E 141 (92.4'), f.p. south 38'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-13) Quarter corner common to Sections 35, T22N, R7W and Section 2, T21N, R7W. Corner was set single proration to Governm corners to the East and West based upon 1923 survey of record. Corner was set in center of East and West gravel road and line with Government corner to West and W. 1/8 corner on Township line which is also the Northeast corner of the subdivision Rainbow Harbor.
- This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13) Set 1/2" rebar with Miss. Co. Remon. Cap

- N16E 32.39' Corner Fe. Post
- S01E 117.66' Power Pole
- S35E 71.70' 10" Spruce
- S54W 38.65' 8" twin elm

Peer Group Reviewed and Approved

Date: 12-30-96  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by \_\_\_\_\_ Date 12-30-96

