

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

1112

For corners in

<u>Missaukee County</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>7W</u>	<u>L-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 308 PAGE 905

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 30 1996 4:30 P.M.

Roslyn Flare

Register of Deeds Stamp & File
Number

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

L-13) 1837 GLO survey by John Brink, Deputy Surveyor, set quarter post - Yellow pine 10" N56E 04, White pine 12" N48W 07
 1977 Jerry L. Wilcox LCRC no. 528, Set 1/2" rod by SP - S05E 20" wild cherry 68.12', S65E 20" wild cherry 118.56', N15E
 power pole 32.00', N30E 12" poplar 94.70'
 1977 Jerry L. Wilcox survey, rec. Liber S1, page 374
 1981 Jerry L. Wilcox survey, rec. Liber S2, page 68
 1981 Jerry L. Wilcox survey, rec. Liber S2, page 36

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13) Quarter corner common to Section 36, T22N, R7W and Section 1, T21N, R7W. Found 1/2" iron and cap (#14102) in centerline of E&W road. This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13) Set Miss. Co. remon. cap on existing iron

N18E	32.02'	power pole (fd. nail)
S02E	67.51'	cherry stump (fd. Nail)
S41E	74.27'	6" cherry
S60E	116.71'	cherry stump
N48W	176.29'	12" tri-cherry
S46W	58.85'	4" cherry clump

Peer Group Reviewed and Approved

Date: 12-30-96
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

Signed by Daniel E. Schripsema
 Surveyor's Michigan License No. 24617

DANIEL E. SCHRIPSEMA
 LAND SURVEYOR
 No. 24617
 REGISTERED LAND SURVEYOR

Date 12-30-96