

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Missaukee (County) Located In: Corner Code #

1. Public Land Survey T 22N R 7W M-5
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
 Private Claims _____

1203
 LIBER 315 PAGE 1105
 MISSAUKEE COUNTY MICHIGAN
 RECORDED DEC 29 1997 ^{1:35} P.M.
Caslyn Flare
 Register of Deeds Stamp & REGISTER Number

I, Daniel E. Schripsema, in a field survey on October 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-5) 1838 GLO set post corner section 12, 13; White Pine 12 S54W 18, Yellow Pine 13 N13W 29

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5) Corner common to Section 12 & 13, T22N, R7W and Section 7 & 8, T22N, R6W. Set 1/2" rebar with Missaukee County Monument by single proration along Township line between M-3 and M-6.

This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


M-5) Set Missaukee County Monument on existing iron

- S48W 10.64' 8"Tri Maple
- S30E 41.42' 6"Tri Maple
- S84E 51.88' 7"Maple
- N13W 34.84' 10"W.Birch

Peer Group Reviewed and Approved
 Date: 12-18-97
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema* Date 12-2-97

Surveyor's Michigan License No. DANIEL E. 24617



SURVEY & REMONUMENTATION

JAN 16 1998

SECTION