

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Missaukee County  
 (County)

Located In:

Corner Code #

1. Public Land Survey		<u>T 22N R 7W</u>	<u>M-6</u>
		T ___ R ___	_____
		T ___ R ___	_____
		T ___ R ___	_____
2. Property Controlling in Section	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____

#1223  
 LIBER 315 PAGE 112

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 29 1997 12

*Carolyn Klare*  
 REGISTER

Register of Deeds Stamp & File  
 Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Daniel E. Schripsema, in a field survey on October 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate**

	A	B	C	D	E	F	G	H	I	J	K
1											
2	6			5			4			3	2
3											
4	7			8			9			10	11
5											
6	18			17			16			15	14
7											
8	19			20			21			22	23
9											
10	30			29			28			27	26
11											
12	31			32			33			34	35
13											

A. Description of original monument and accessories and/or subsequent restoration:

M-6) 1838 GLO survey set quarter post section 13; Tamarack 8 S54W 8, do 8 N24W 11

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6) Corner common to Section 13, T22N, R7W and Section 18, T22N, R6W. Found 1 3/4" x 12" pipe with cap filled with concrete and remains of concrete base attached laying horizontal, replaced with 3/4" x 36" rebar and Missaukee County monument in the center of concrete base remains at base of pipe.  
 This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6) Set 3/4" x 36" rebar and Missaukee County Monument  
 N50W 17.05' 6" Maple  
 N10W 11.06' 4" W. Birch  
 East 8.08' 16" Tamarack  
 S30W 35.99' 12" Tamarack

Peer Group Reviewed and Approved

Date: 12-23-97  
*J. Dean Geers*  
 J. Dean Geers, Missaukee Co. Representative

Signed by: *Daniel E. Schripsema*  
 Surveyor's Michigan License No. 24617

Date: 12-2-97



**SURVEY &  
 REMONUMENTATION**

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1  
 REVISED MAY 14, 1  
 REVISED JAN., 1  
 REVISED OCT., 1

JAN 16 1998

SECTION