

OCT 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Missaukee County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>7W</u>	<u>M-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

# 1227  
LIBER 315 PAGE 1129

MISSAUKEE COUNTY MICHIGAN  
RECORDED DEC 29 1997 125 P.M.  
*Angela Flor*  
Register of Deeds Stamp File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Daniel E. Schripsema, in a field survey on October 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- M-9) 1837 GLO survey set post corner sections 24, 25; Beech 10 S43W 40, do 11 N61W 34 +/-1900 Beuthien survey, FB #34, pg. 93, county surveyor notes; Maple NE 48.5, Cor. FP SE 45.0, Cor. FP West 37.5
- 1898 Beuthien survey, FB #37, pg. 75, county surveyor notes; Iron bolt 20" long, 1 1/2" in diameter in place of stake
- 1907 Beuthien survey, FB #33, pg. 74, county surveyor notes; set Cedar stake
- 1913 Beuthien survey, FB #33, pg. 68, county surveyor notes; Cedar fence post N46E 64
- 1916 Beuthien survey, FB #9, county surveyor notes; Iron Post, Cor. Fence Post N46E 64
- 1930 Beuthien survey, FB #34, pg. 68, county surveyor notes;
- 1976 Jerry L. Wilcox LCRC, #193; set R.R. Spike  
S80W Cor. Fe. Post 33.70, S55E 12" Dbl. Maple 135.55, N40E 8" J. Pine 63.65
- 1980 Jerry L. Wilcox LCRC, #590; Fd. 3/4" Gas Pipe, this corner superseded 1976 LCRC  
N41E 8" J. Pine 61.44, N45W 8" Square Fence Post 52.92, West Corner Fence Post 38.43, West centerline N-S Rd. 1.5
- 1995 Craig J. Pullen survey, liber S-3, pg. 323; Fd. R.R. Spike  
N79E 20" Jack Pine 97.80, S58W 9" Red Pine 56.83, N53W North Gate Post 47.21

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9) Corner common to Sections 24 & 25, T22N, R7W and Sections 19 & 30, T22N, R6W. Found 1/2" rerod/cap of record. Corner falls 2' East of centerline of intersection of roads North, South and East.

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9) Set Missaukee County monument on existing 1/2' rerod  
N45W 52.92 8" sq., fe. post (LCRC #590)  
S87W 38.43' corner fence post (LCRC #590)  
S75E 130.50' 12" double Maple (LCRC #193)  
N37E 61.44' 8" Jack Pine (LCRC #590)  
N70E 97.80' 20" Jack Pine \*

Peer Group Reviewed and Approved  
Date: 12-23-97  
*[Signature]*  
Dean Geers, Missaukee Co. Representative

Signed by *[Signature]*  
Surveyor's Michigan License No. 24617

Date 12-2-97

