

OCT 24 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Missaukee County
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 22N R 7W M-11
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

#1229
LIBER 315 PAGE 1131
MISSAUKEE COUNTY MICHIGAN
RECORDED DEC 29 1997 ¹²⁵ P.M.
Carolyn Klare
Register of Deeds Stamp & File Number

I, Daniel E. Schripsema, in a field survey on October 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- M-11) 1837 GLO survey - Hemlock 14" diameter named corner of sections 25, 36
- 1898 Beuthien survey, FB #33, pg. 73, county surveyor notes; WPS 21 N23E 97, WPS 24 S05E 53
- 1916 Beuthien survey, FB #9, pg. , county surveyor notes; R.R. Iron, WPS 24 N24E 97, Cor. FP N43W 66
- 1930 Beuthien survey, FB #34, pg. 68, county surveyor notes; Iron Post, FP N43W 43.6', WPS N24E 63'
- 1982 Jerry L. Wilcox survey, liber S-2, pg. 118; Fd. 3/4" Pipe
- N41E 61.44 8" J. Pine, N45W 52.92 8" J. Pine, West 38.43 cor. fe. post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-11) Corner common to Sections 25 & 36, T22N, R7W and Sections 30 & 31, T22N, R6W. Corner of record was removed during road construction.
- Corner was reset using bearings and distances from survey of record (S-2, pg. 118) - quarter corners west, south, north and found 1/2" rerod/cap 33' south and west of corner. This corner is accepted as a careful and faithful reestablishment of position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-11) Set Missaukee County Monument on 1/2" rerod
- N22W 111.30' 12" W. Pine
- N49E 47.06' 4" sq. post at telephone riser
- S22E 69.10' Gas line marker
- S68W 53.28' Stop sign post

Peer Group Reviewed and Approved

Date: 12-23-97
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema*
Surveyor's Michigan License No. 24617

Date 12-2-97

