

**SURVEY &
REMONUMENTATION**

MAY 28 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

1111

For corners in

<u>Missaukee County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>7W</u>	<u>K-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

LIBER 308 PAGE 904

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 30 1996 4:30 p.m.

Paulyn Klare
REGISTER
Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel E. Schripsema, in a field survey on October 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11			
5												
6	18		17		16		15		14			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												

A. Description of original monument and accessories and/or subsequent restoration:

- K-13) 1837 GLO survey by John Brink, Deputy Surveyor, set post - white pine 24" N54E 45, beech 10" N80W 38
- 1911 Beuthien survey, Sec. 2, T21N, R7W, pg. 84 co. surveyor field notes Stone - w.p.s. 30" N61E 105
- 1923 survey of Sec. 35, T22N, R7W, pg. 91, co. surveyor field notes - stone-w.p.s. 30" N61E 105 (69.3'), w.p.s. 30" S53E 80 (52.8')
- 1977 Jerry L. Wilcox LCRC pg. 528, found 3/4" iron pipe - S10E 15" wild cherry 26.53', S45W power pole 48.18', S25E 8" white pine 62.08', N30E 6" poplar 103.51'
- 1977 Jerry L. Wilcox survey, rec. Liber S1, pg. 374
- 1981 Jerry L. Wilcox survey, rec. Liber S2, pg. 36 - fd. 3/4" iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13) Section corner common to Sections 35 & 36, T22N, R7W, and Sections 1 & 2, T21N, R7W. Found 3/4" iron pipe of record, 2' South of centerline E&W road, centerline of road North, and 10' East of centerline 2-track South. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-13) Set Miss. Co. remon cap on existing iron
- S56W 48.06' Power pole (fd. Nail)
- S04E 26.53' twin 16" cherry (fd. Nail)
- S18E 62.20' 10" white pine (fd. Nail)
- N49W 58.55' 4" x 4" post @ phone riser
- S76W 82.77' 24" maple

Peer Group Reviewed and Approved

Date: 12-30-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Date 12-30-96

