

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 23 N.R. 5 W


Missaukee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 10-11

CORNER MONUMENT Set 1" pipe with 4" aluminum cap below surface

DATE MONUMENT PLACED AND WITNESSED 5-9-67

WITNESSES TO CORNER.....



12" S. Maple N 58 W 45.5°

10" Elm S 28 E 36.1°

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during a survey in this area. Found old iron bedpost buried at corner, in line with fence south, and about 3' north of center of road. Established in old county survey.

SURVEYOR'S SEAL

SIGNED _____ DATE 5-25-67
REGISTERED LAND SURVEYOR #10068