

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S 24 T 23N R 5W	<u>8</u>
	S 24 T 23N R 5W	<u>11</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**Register of Deeds Stamp & File Num**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Craig W. McVean, in a field survey on March 6, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

8 - None. 11 - None.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

8 - C-W 1/16 Sec. 24 - Set 2" A.C. on 5/8" x 34" Rebar in swamp per Standard BLM Procedure. 11 - SW 1/16 Sec. 24 - Set 2" A.C. on 5/8" x 34" Rebar per Standard BLM Procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>8</u> - 2" A.C. on 5/8" x 34" Rebar with Carsonite Post 1' NE. N64°E 71.59' to N&T in N. Side 5" J. Pine S75°E 75.87' to N&T in NE Side 12" R. Pine S45°E 79.22' to N&T in E. Side 1" R. Pine S28°E 85.91' to N&T in W. Side 10" J. Pine	<u>11</u> - 2" A.C. on 5/8" x 34" Rebar with Carsonite Post 1' NE. S33°E 44.30' to N&T in NE Side 10" W. Birch S40°W 33.93' to N&T in SE Side 2" R. Pine N40°W 51.75' to N&T in SW Side 10" J. Pine N48°E 100.95' to N&T in 14" R. Pine
---	---

Signed by Craig W. McVean  
 Surveyor's Michigan License No. 39088

Date 3/6/1998